

Projects

[LichteFeld Inc](#) > [Projects](#) > Hams Medical Plaza II

Hams Medical Plaza II

Medical Projects



Square Feet

24,000 s.f.



Project Location

Shelbyville Road - Middletown, Kentucky



Construction Dates

2000



End User

Multi tenant office space



Property Details

20,000 s.f. medical professional office facility located in Middletown on Shelbyville Road.

This building is conventionally constructed. Custom engineered superstructure with beam and post primary structurals, bar joist metal deck on 2nd floor, poured in pan concrete floors, steel stairs with poured in pan risers. The roof is also beam and post primary structurals with bar joist metal deck subbase with EPDM roof systems.

The exterior is made of metal studs, sheathing, exterior insulated finish systems, aluminum insulated storefront glass windows and doors.

The project is designed and built by LichteFeld, Inc.

PDF

FacebookLinkedInTwitterShare