



Ninth and O Baptist Church

Projects

[LichteFeld Inc](#) > [Projects](#) > Ninth and O Baptist Church

Ninth and O Baptist Church

Schools and Churches



Square Feet

26,000 s.f.



Project Location

Breckenridge Lane - Louisville, Kentucky



Construction Dates

Start: March 2004 - Complete: October 2004



End User

Congregation of Ninth and O

























Property Details

26,000 s.f. addition, two-story educational facility. This is a Butler metal building structure with conventional steel building accents and wood framing with metal panels on exterior. It has an MR-24 standing machine seamed roof system. The wall system is composed of concrete tilt-wall, brick, and Butler Texture Cote wall panels. Other materials used for this project; brick, block, storefront glass and Dryvit. This was a phased project that was built while Ninth and O was in operation. There were several coordination meetings and plenty of concessions made to accommodate the client while under construction. * month project completed on time and in budget.

This project was designed by LichteFeld, Inc. and Berry-Prindle Architects.

Engineered by LichteFeld, Inc. and AGR Civil Engineers.



Ninth and O Baptist Church

Design/Build project by LichteFeld, Inc.